REPLIES OF QUERIES

Name of Work: "REFURBISHMENT OF INTERIOR WORK AT 1ST FLOOR AT ASSAM WATER FOR HYDRO- INFORMATICS UNIT"

RFQ No: FREMAA(P)/TECH/48/2022/14, Dated-30th August2022

SL. NO	QUERIES OF BIDDER	REPLY OF FREMAA		
1.	Tend.SI.No.:1.1 Finishing materials of existing partition: Mention 1.5 mm laminates readily no company keep stock and against order it comes from manufacturer factory. Naturally company takes the minimum 30 days. Please note that 1.0mm readily available. N.B: Please note that in furniture item no. 9.03 mention 1.0mm Laminates	Item to be used as specified in the BOQ. Asper market enquiry/survey, it was found that the indicated materials delivery time takes a maximum of 15 to 20 days in case of procurement of the item.		
2.	Tend. SI.No.2.02 Glass Door with SS Handle -3 Nos (Size not mentioned)	Standard Size of Glass Door handle shall be 40 cm (Please refer to the Corrigendum-I)		
3.	Tend.SI.No.7.01 Storage cabinet: Finishing materials for external and internal not specified	Quantity of finishing material has already been considered in laminate item. (Please refer to BoQ item Sl. no.1.3)		
4.	Tend.SI.No.8.03 Aluminum Window: Colour of anodized if required and thicknessas per micron. Colour: Self/Bronze or Brown —which one	Any color of anodized Aluminum Window may be proposed. (Please refer to the Corrigendum-I)		
5.	Tend SI.No.:8.04 Flush Door: Make at least 3 instead of one and thickness of flush door & Size-? Finishing — Paint/Laminates/Veneer-which one	Make of Flush door shall be as specified in BOQ or equivalent or Higher. Size of Flush is: Thickness:35mm, Length -7ft, Width-3ft. Finishing: Laminate (Please refer to the Corrigendum-I)		
6.	Tend SI.No.:8.07 Glass Partition includes door or only fixed partition exclude door	As specified in the Drawing of the RFQ.		

7.	Tend SI.No.:9.02 "L" Shape Worktop: Finishing Materials? Pedestal Unit for writing desk-Required or not, Credenza- With Storage?	"L" Shape Works top: Finishing Materials- Yes Pedestal Unit for writing desk-Required or not: Required. Credenza- With Storage? – Yes (Please refer to the Corrigendum-I)
8.	Tend SI.No.:9.02 Laminates for existing flush door with 6m ply+ laminates: As required door frames needs modification due to thickness Variation of flush door fixing.	As per site execution.

Corrigendum-I

Date:12.09.2022

In reference to the Request for Quotation (RFQ) no. FREMAA(P)/TECH/48/2022/14, dated 30th August 2022 for "Refurbishment of Interior Work at 1st Floor at Assam Water Centre (AWC) for Hydro Informatics Unit" certain amendments/incorporations are made in the Bill of Quantities (BoQ) of the RFQ as detailed below:

Sl. no	BoQ item Sl. no.	Original item Descriptions in the BoQ	Qty	Unit	Item Description(modified) in the BoQ may be read as follows:	Qty	Unit
1	2.02	Glass door with SS Handle, Floor Spring & Lock -12mm	3	No	Glass door with SS Handle, Floor Spring & Lock - 12mm.Glass door Handle size is 40 cm	3	No
2	8.03	Dismantling Bricks works and creating window opening at Control Room providing Fixed Glass Window of size 1800 x 1200 size with 6mm thick glazing fixed to Aluminums section of appropriate size.	4	No	Dismantling Bricks works and creating window opening at Control Room providing Fixed Glass Window of size 1800 x 1200 size with 6mm thick glazing fixed to Aluminums section of any colour of appropriate size.	4	No
3	8.04	Flush Door (Cabin, Balcony Door) MAKE- ARCHIDPLY	6	No	Flush Door (Cabin, Balcony Door) MAKE-ARCHIDPLY or equivalent or Higher. Size: 35mm Thick, Length - 7ft, Width- 3ft. Finishing: Laminate	6	Nos
4	9.02	L-shaped arrangement	3	No	L-shaped arrangement of rectangular worktops with	3	No.

of rectangular worktops of overall dimension 3750mm L1 x 2850mm L2 x 600mm D as per the layout approved by the consultant	finished materials of overall dimension 3750mm L1 x 2850mm L2 x 600mm D along with the Pedestal Unit for writing desk and Credenza- with Storage as per the layout approved by the client's engineer i/c	
the consultant		

The last date & time of online submission of quotation through e-procurement portal is 19.09.2022 at 14:00HRS

Sd/(Dr. Jeevan B, IAS)
Chief Executive Officer-FREMAA